



# INSPECTION REQUIREMENTS CHECKLIST FOR PLUMBING, GAS, MEDICAL GAS, AND IRRIGATION

## Plumbing

- Underground sanitary and water test.
- Above-ground sanitary test.
- Above-ground water test.
- Tub/shower install and test.
- Grease interceptor/sewer inspection.
- Final inspection.

## Gas

- Underground inspection.
- Above-ground, in wall inspection and test.
- Final inspection.

## Medical Gas

- Above-ground in wall inspection and test.
- Final.

## Irrigation

- Piping and required controls inspection.
- Final.

**This document is intended to be a guide and may not contain all requirements needed to obtain permits and approval from the City of Orlando.**

*....To operate a permitting agency that is customer service oriented while protecting public safety through clear, consistent code application while ensuring Orlando's economic competitiveness.*

---

**ECONOMIC DEVELOPMENT DEPARTMENT•OFFICE OF PERMITTING SERVICES**  
CITY HALL•400 SOUTH ORANGE AVENUE•FIRST FLOOR•P.O. BOX 4990•ORLANDO, FLORIDA 32802-4990  
PHONE 407.246.2271•FAX 407.246.2882

Visit our web site at: [www.cityoforlando.net/permits](http://www.cityoforlando.net/permits)

# **MOST COMMON REASONS FOR DISAPPROVAL**

## **Underground Sanitary and Water**

1. Incorrect slope on sewer and drainage piping.
2. No pressure test on drainpipe and/or water pipe.

## **Sanitary Drain Pipe**

1. Incorrect venting.
2. No test on pipe.
3. Incorrect fittings used.
4. Hangers and supports missing.
5. Incorrect slope on drainpipe in the walls and/or above ceiling.

## **Water Pipe**

1. No pressure test and/or test gauge to read pressure.
2. Hangers and/or supports missing.
3. Incorrect type of pipe and/or type of fittings.
4. Incorrect size of piping to supply fixtures.

## **Tub/Shower and/or Shower**

1. Water test required.
2. 2% slope required under shower liner.

## **Sewer**

1. No test.
2. Incorrect slope on pipe.
3. Clean outs missing or in wrong location.

## **Final Inspection**

1. Unable to gain access to building.
2. Fixtures not grouted or caulked (water tight seal at floor).
3. Fixtures not installed.

*....To operate a permitting agency that is customer service oriented while protecting public safety through clear, consistent code application while ensuring Orlando's economic competitiveness.*

---